Exhibit A.13



Land Use Planning Division 1600 SE 190th Ave.

Portland OR 97233 Phone: 503-988-3043

land.use.planning@multco.us https://multco.us/landuse/

	F	REVIE	WED			
MULTNOMAH COUNTY - DCS						
TRA	NSPC	RTA	TION DI	IVISION		
	Α.	PRC	CEED			
/	B.	PRO	CEED	AS NOTED		
	C.	REV	'ISE AN	D RESUBMIT		
By Loden of	'AAn	~	Date:	06/22/2021		

STORMWATER DRAINAGE CONTROL CERTIFICATE >500 SQUARE FEET OF NEW / REPLACED IMPERVIOUS SURFACES

NOTE TO PROPERTY OWNER/APPLICANT: Please have an Oregon Licensed Professional Engineer fill out this Certificate and attach a signed site plan, stamped and signed storm water system details, and stamped and signed storm water calculations used to support the conclusion. Please note that replacement of existing structures does not provide a credit to the square footage threshold.

that replacement of exist	ing structures does not provide a credit to the square footage threshold.
	23414 NW Moreland Rd
Property Address or Lo	egal Description: North Plains, OR 97133
Description of Project:	Project is the construction of a new storage building (See A5.0). Seeking the following: 1. Significant Environmental Concern (Type 2) permit for a new 2.375 SF accessory storage building and retro-active permit for an existing 880 SF water well ag building (See A101). 2. Accessory Use Determination (total area of accessory building exceeds 2,500 SF) 3. Geologic Hazard exemption
The following stormwater	er drainage control system will be required:
Natural Infil	r, downspout, and splash block drainage control system; tration Process; or of an on-site storm water drainage control system.
The rate of stormwater r	anoff attributed to the new/replaced development for a 10-year/24-hour storm

The rate of stormwater runoff attributed to the new/replaced development for a 10-year/24-hour storm event will be no greater than that which existed prior to any development as measured from the property line or from the point of discharge into a water body with the use of the designated system [MCC 39.6235].

I certify the attached signed site plan showing the areas needed for the chosen system type, stamped and signed storm water system design details, and stamped and signed calculations dated 692020 will meet the requirements listed above.

Signature:	Engineer's Stamp Below:
Print Name: CONNOR LAMB	TERED PROFES
Business Name:	B4011PE
Address: 18829 NW LOGIE TRAIL, RD.	Car Tha
Phone #: (360)977.8056	23, 2013 to
Date: $6/9/2021$	EXPIRES 12/31/2022

NOTE TO ENGINEER: Please check one box above. Multnomah County does not use the City of Portland's storm water ordinance. As part of your review, MCC 39.6235 requires that you must consider all new, replaced, and existing structures and impervious areas and determine that the newly generated stormwater from the new or replaced impervious surfaces is in compliance with Multnomah County Code for a 10-year/24-hour storm event. This Storm Water Drainage Control Certificate does not apply to shingle or roof replacement on lawfully established structures.

Storm Water Certificate

§ 39.6235 STORMWATER DRAINAGE CONTROL.

- (A) Persons creating new or replacing existing impervious surfaces exceeding 500 square feet shall install a stormwater drainage system as provided in this section. This subsection (A) does not apply to shingle or roof replacement on lawful structures.
- (B) The provisions of this section are in addition to and not in lieu of any other provision of the code regulating stormwater or its drainage and other impacts and effects, including but not limited to regulation thereof in the SEC overlay.
- (C) The provisions of this section are in addition to and not in lieu of stormwater and drainage requirements in the Multnomah County Road Rules and Design and Construction Manual, including those requirements relating to impervious surfaces and proposals to discharge stormwater onto a county right-of-way.
- (D) The stormwater drainage system required in subsection (A) shall be designed to ensure that the rate of runoff for the 10-year 24-hour storm event is no greater than that which existed prior to development at the property line or point of discharge into a water body.
- (E) At a minimum, to establish satisfaction of the standards in this section and all other applicable stormwater-related regulations in this code, the following information must be provided to the planning director:
 - (1) A site plan drawn to scale, showing the property line locations, ground topography (contours), boundaries of all ground disturbing activities, roads and driveways, existing and proposed structures and buildings, existing and proposed sanitary tank and drainfields (primary and reserve), location of stormwater disposal, trees and vegetation proposed for both removal and planting and an outline of wooded areas, water bodies and existing drywells;
 - (2) Documentation establishing approval of any new stormwater surcharges to a sanitary drainfield by the City of Portland Sanitarian and/or any other agency authorized to review waste disposal systems;
 - (3) Certified statement, and supporting information and documentation, by an Oregon licensed Professional Engineer that the proposed or existing stormwater drainage system satisfies all standards set forth in this section and all other stormwater drainage system standards in this code; and
 - (4) Any other report, information, plan, certification or documentation necessary to establish satisfaction of all standards set forth in this section and all other applicable stormwater-related regulations in this code, such as, but not limited to, analyses and explanations of soil characteristics, engineering solutions, and proposed stream and upland environmental protection measures.

Storm Water Certificate Rev. 09/11/2019

A Q OF STORMWATER ATTRIBUTED TO THE NEW DEVELOPMENT USING A SENSITIVITY ANALYSIS WITH THE PATIONAL METHOD

SHED FOOTPRINT = 1240 C+2 = 0.028 ACRES

RUNOFF COEFFICIENTS FOR THE RATIONAL METHOD (ODOT HYDRAUG)

HOUSE = FINGHED SELOND + ATT GAR + GR HOUSE

3223 ft2 + 1142 ft2 + 128 ft2 = 4493 ft2 = 0.10 Acres

CONCRETE PAVEMENT = 1600 Fr2 = 0.04 ACRES

BRICK PANING = 6000 f+2 = 0.14 ACRES

OTHER IMPERVIOUS = DECK + COV PATED + POOL

= 140 ft2+ 400 ft2+ 800 ft2= 1340 ft2= 0.03 AC DRIVEWAY (GRAVEL) = 10,000 \$42 = 0.23 ACRES

Tost = 0.93 (Lo.6 no.6)

Tose = TRAVEL TIME FOR OVERLAND SHEET FLOW SEGMETRIT (MIN.)

L = LENGTH OF FLOW = 300 F+

1 = MANNING'S ROUGHNESS COEFFICIENT = 0.4 (WOODLAND FROKESTS)

i = RAINFALL INTENSITY (in/hr) = FROM GRAPH

5 = AVENAGE SLOPE : = 10% = 0.10

ASSUME TO 30 MID. IDR ZONE 8 (ODOT THELE ATTHCHEN)

Te = 0.73 (300 0.00) A = 0.150

USE EXCEL TABLE FOR TO (HERATIVE PROCESS) ATTACHED

START WITH T = 3/

i = 1.0

TC(CALC) = 32.8

2ND ITERATION

 $T_{c} = 33$ i = 0.96 T

Tyraus 33.3

SEB CALC SHEET

										Qexisting	9.4		Q _{New}	9.4	
				0.15		0.11		0.20		1.18		8.00	9.64	0.03	99.6
AREA (AC)	0.10	0.04	0.03	0.17	0.14	0.14	0.23	0.23	2.15	2.15	40.01	40.01	42.70	0.03	42.70
AREA (SF)	4493	1600	1340	7433	0009	0009	10000	10000	93640	93640		NA		1240	
C				06.0		08.0		0.85		0.55		0.20		06.0	
	House	Concrete Pavement	Other Impervious	Total Pavement & Roofs	Brick Pavers	Total Drives & Walks	Gravel Drive Around Shed	Total Gravel Pavement	Vineyard	Total Cultivated Land, Clay & Loam	Unimproved Forest Area (>10% slopes)	Total Woodland & Forests	Total Existing	Tractor Parking and Well Shed	
			S	əət	3171	nS	Bu	its	İΧΞ	I				New	

Assume $T_c = 33$,

Assume $T_c = 31$

i = 1.0

i = 0.96

300

300

0.4

п

0.96

п

I calc =

32.8089

Lcalc =

S

42.70

96.0

0.23

42.70

96.0

0.23

S

Using the rational method to find the peak flow rate for the existing condition and the new condition shows that Qexisting = Qnew. Therefore, the rate of stormwater runoff attributed to the Tractor Parking and Well Shed was shown to be no greater than that which existed prior. Conservative values including a shortened flow C(new) length and Runoff Coefficients (C values) were used.

0.23

C(exist)

Downspout extensions, splash blocks, and/or other flow dispusion methods to overland infiltration on the property should be used.

Note: Single family residential roof drains are exempted from the Oregon UIC program.

Projects are excluded from application of Oregon's water quantity performance standard when the uncontrolled peak post-construction runoff rate from the net new impervious surface area is less than 0.5 cubic feet per second during the 10-year, 24-hour storm event from the total proposed contributing area.


concentration and a runoff coefficient of 0.90 for impervious surface, using the Rational Method yields a peak flow rate of 0.49 cubic feet per second. This project For example, in the Zone 8 (Project Location) 0.5 cfs is generated from a proposed development area of approximately 0.24 acre. In this case, using the ODOT Hydraulics Manual (Chapter 7), for Zone 8 the rainfall intensity for a 10-year storm is 2.3 inches/hour. For an area of 0.24 acre, assuming a 5-minute time of impervious area results in 0.03 acres which is less than 0.24 acres; therefore yielding much less than 0.5 cubic feet per second.

Table 1 Runoff Coefficients for the Rational Method

	FLAT	ROLLING	HILLY
Pavement & Roofs	0.90	0.90	0.90
Earth Shoulders	0.50	0.50	0.50
Drives & Walks	0.75	0.80	0.85
Gravel Pavement	0.85	0.85	0.85
City Business Areas	0.80	0.85	0.85
Apartment Dwelling Areas	0.50	0.60	0.70
Light Residential: 1 to 3 units/acre	0.35	0.40	0.45
Normal Residential: 3 to 6 units/acre	0.50	0.55	0.60
Dense Residential: 6 to 15 units/acre	0.70	0.75	0.80
Lawns	0.17	0.22	0.35
Grass Shoulders	0.25	0.25	0.25
Side Slopes, Earth	0.60	0.60	0.60
Side Slopes, Turf	0.30	0.30	0.30
Median Areas, Turf	0.25	0.30	0.30
Cultivated Land, Clay & Loam	0.50	0.55	0.60
Cultivated Land, Sand & Gravel	0.25	0.30	0.35
Industrial Areas, Light	0.50	0.70	0.80
Industrial Areas, Heavy	0.60	0.80	0.90
Parks & Cemeteries	0.10	0.15	0.25
Playgrounds	0.20	0.25	0.30
Woodland & Forests	0.10	0.15	0.20
Meadows & Pasture Land	0.25	0.30	0.35
Unimproved Areas	0.10	0.20	0.30

Note:

- Impervious surfaces in bold
- Rolling = ground slope between 2 percent to 10 percent
- Hilly = ground slope greater than 10 percent




(
[1	
1		
		ď
i	•	
i	i	,
(
	2	2
	3	
	2	
	7	i
•	Š	Ì
2		
0	TO WIND TO TO TO	1
		1
	· · · · · · · · · · · · · · · · · · ·	
	· · · · · · · · · · · · · · · · · · ·	
	· · · · · · · · · · · · · · · · · · ·	
	· · · · · · · · · · · · · · · · · · ·	


11/6/2018

Segment Number	Segment Type	Class	Area Sq Ft
1	MAIN	NZ	2940
2	FIN SECOND	NZ	3223
6	FIN BSMT	NZ	2064
4	UNF BSMT	N	728
ы	UNF BSMT	NZ	1350
9	ATT GAR	NZ	1142
7	GR HOUSE	NZ	128
co	CONCRETE	N	1600
O	BRICK PAV	N	0009
10	DECK	N	140
11	COV PATIO	N	400
12	POOL	N	800

_
8
Ö.
₩

MyTopo Map Print





MAP INFORMATION

MAP LEGEND

The soil surveys that comprise your AOI were mapped at 1:20,000.

Warning: Soil Map may not be valid at this scale.

contrasting soils that could have been shown at a more detailed misunderstanding of the detail of mapping and accuracy of soil Enlargement of maps beyond the scale of mapping can cause line placement. The maps do not show the small areas of scale.

Not rated or not available

C/D

Soils

Streams and Canals

Please rely on the bar scale on each map sheet for map measurements. Source of Map: Natural Resources Conservation Service Web Soil Survey URL:

Coordinate System: Web Mercator (EPSG:3857)

distance and area. A projection that preserves area, such as the Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required. This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Multnomah County Area, Oregon Survey Area Data: Version 16, Sep 17, 2018

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger. Date(s) aerial images were photographed: Sep 29, 2015—Sep 13, 2016

Not rated or not available

C/D

Soil Rating Points

70

S

 8/0

8

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Interstate Highways

Rails

Major Roads Local Roads

US Routes

USDA

Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
7C	Cascade silt loam, 8 to 15 percent slopes	С	4.8	10.9%
7D	Cascade silt loam, 15 to 30 percent slopes	С	7.0	16.2%
7E	Cascade silt loam, 30 to 60 percent slopes	С	31.8	72.9%
Totals for Area of Inter	rest	1	43.6	100.0%

Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

Rating Options

Aggregation Method: Dominant Condition
Component Percent Cutoff: None Specified

Tie-break Rule: Higher